

EXHIBIT A

**DEPARTMENT OF PUBLIC WORKS AND PLANNING
2016/ 2017 BITUMINOUS SEAL COATS CONTRACT
NO. 16-18-C**

BASE BID -BITUMINOUS SEAL COATS

NO.	PROJECT LOCATION	LIMITS		LENGTH (miles)	WIDTH (feet)	SURFACE AREA (SY)	PMCRS-2h EMULSIO N (tons)	MEDIUM CHIPS (tons)	FOG SEAL EMULSIO N (tons)	SAND (tons)	COMMENTS
1	CLAYTON	CALAVERAS	SAN MATEO	1.973	24	27780	39.0	365.0	8.0	88.0	ANS
2	DOUGLAS	ADAMS	ORMSBY	0.736	22	9500	14.0	125.0	3.0	30.0	ANS
	ORMSBY	DOUGLAS	MANNING	1.346	20	15794	23.0	208.0	5.0	50.0	ANS
3	RUSSELL	SHIELDS	SHAW	2.001	24	28175	40.0	370.0	8.0	89.0	ANS
4	HUDSON	SR 33	MERRILL	2.798	24	39396	56.0	518.0	11.0	125.0	ANS
5	FAIRFAX	BULLARD	NEES	2.041	24	28738	41.0	378.0	8.0	91.0	ANS
6	WASHOE	BULLARD	NEES	2.288	24	32216	46.0	423.0	9.0	102.0	ANS
7	DE WOLF	JENSEN	AMERICAN	3.032	24	42691	60.0	561.0	12.0	135.0	ANS
8	ELWOOD	SR 180	LUPINE	5.768	24	81214	114.0	1,066.0	22.0	256.0	ANS
9	MARKS	CONEJO	ELKHORN	1.996	24	28104	40.0	369.0	8.0	89.0	
10	HILL	SUMNER	MANNING	1.499	24	21106	30.0	278.0	6.0	67.0	ANS
TOTAL BASE BID				25.478		354,714	503.0	4661.0	100.0	1122.0	

ANS = Advance Notification Signs install one week prior to starting work.

ANS* = Install two weeks prior to starting work at this location.

ADDITIVES 1A-9A

NO.	PROJECT LOCATION	LIMITS		LENGTH (miles)	WIDTH (feet)	SURFACE AREA (SY)	PMCRS-2h EMULSIO N (tons)	MEDIUM CHIPS (tons)	FOG SEAL EMULSIO N (tons)	SAND (tons)	COMMENTS
1A	FOWLER	AMERICAN	0.125 S/O CLAYTON	1.631	24	22965	33.0	302.0	7.0	73.0	ANS
2A	COVE	SR 180	JENSEN	0.741	24	10434	15.0	137.0	3.0	33.0	ANS
3A	SOUTH	HIGHLAND	ACADEMY	3.980	24	56039	79.0	736.0	15.0	177.0	
4A	MARKS	SOUTH	FLORAL	2.995	24	42170	60.0	554.0	12.0	133.0	
5A	TRIMMER SPRINGS	SR 180	BELMONT	2.120	22	27363	39.0	360.0	8.0	87.0	
6A	RIO VISTA	SR 180	TRIMMER SPRINGS	0.922	20	10819	16.0	142.0	3.0	35.0	
7A	CRAWFORD	MANNING	FLORAL	2.000	24	28160	40.0	370.0	8.0	89.0	
8A	CRAWFORD	SR 180	JENSEN	1.000	24	14080	20.0	185.0	4.0	45.0	
9A	JENSEN	SR 145	BUTTE	5.023	24	70724	100.0	929.0	19.0	223.0	
TOTAL BASE BID				20.412		282,754	402.0	3446.0	79.0	895.0	