

EXHIBIT A

DEPARTMENT OF PUBLIC WORKS AND PLANNING
2016-17 BITUMINOUS SEAL COATS
CONTRACT NO. 16-18-C

BASE BID - BITUMINOUS SEAL COATS

NO.	PROJECT LOCATION	LIMITS		LENGTH (miles)	WIDTH (feet)	SURFACE AREA (SY)	PMCRS-2h EMULSIO N (tons)	MEDIUM CHIPS (tons)	FOG SEAL EMULSIO N (tons)	SAND (tons)	COMMENTS
1	CLAYTON	CALAVERAS	SAN MATEO	1.973	24	27780	39.0	365.0	8.0	88.0	ANS
2	DOUGLAS	ADAMS	ORMSBY	0.736	22	9500	14.0	125.0	3.0	30.0	ANS
3	ORMSBY	DOUGLAS	MANNING	1.346	20	15794	23.0	208.0	5.0	50.0	ANS
4	RUSSELL	SHIELDS	SHAW	2.001	24	28175	40.0	370.0	8.0	89.0	ANS
5	HUDSON	SR 33	MERRILL	2.798	24	39396	56.0	518.0	11.0	125.0	ANS
6	FAIRFAX	BULLARD	NEES	2.041	24	28738	41.0	378.0	8.0	91.0	ANS
7	WASHOE	BULLARD	NEES	2.288	24	32216	46.0	423.0	9.0	102.0	ANS
8	DE WOLF	JENSEN	AMERICAN	3.032	24	42691	60.0	561.0	12.0	135.0	ANS
9	ELWOOD	SR 180	LUPINE	5.768	24	81214	114.0	1,066.0	22.0	256.0	ANS
10	MARKS HILL	CONEJO	ELKHORN	1.996	24	28104	40.0	369.0	8.0	89.0	ANS
TOTAL BASE BID		SUMNER	MANNING	1.499	24	21106	30.0	278.0	6.0	67.0	ANS
				25.478		354,714	503.0	4661.0	100.0	1122.0	

ANS = Advance Notification Signs install one week prior to starting work.
ANS* = Install two weeks prior to starting work at this location.