Upgrades, Scope and/or Schedule Change Acknowledgment

This Acknowledgment is made in accordance with Section 11 of the Special Conditions, as defined in that Energy Service Agreement – Solar, between County of Fresno, a political subdivision of the State of California ("Purchaser") and FFP BTM Solar, LLC ("Provider"), dated December 12th, 2023 (the "Agreement") for the Fresno County- Animal Control located at 1510 W Dan Ronquillo Dr., Fresno CA, 93706 (the "Project"). Upon execution by both Purchaser and Provider, this Acknowledgment shall be effective as of _____ , 2026 (the "Acknowledgment Effective Date").

1. Type of Change:

   ☐ Distribution Upgrades (ITC Eligible)
   ☐ Scope Changes (ITC Eligible)
   ☒ Scope Changes (Non-ITC Eligible)
   ☐ Day for Day Extension
   ☐ Extension for Good Cause
   ☐ Other:

2. Description of Change.
   i. Scope Changes (Non-ITC Eligible)

ADA Upgrades
- Mill 1.5" of existing asphalt to remove existing thermoplastic paint that is causing slope issues and low spots in asphalt.
- Pave back with 1.5" of 1/2" hot HMA asphalt to be rolled and compacted.
- Saw cut and remove 247sq.ft of truncated domes.
- Replace with wet set truncated domes on 247sq.ft.

Turf Replacement
- Complete removal and replacement of turf lining the dog runs.

Security Camera Relocation
- Remove and reinstall the security camera from pole to the building.

Remove Fence and Install New Service Gate
- 136' of 7' tall 9g galvanized 3.5"x5.5" Mesh - Privacy Chain Link fence with a 2' wide 9g galvanized 2" Mesh - Anti-climb on top of the fence
- Existing terminal posts are 2-7/8" Diameter Sch40 - To remain in place
- Line posts will be 2-3/8" Diameter Sch40 - Max Spacing 10' O.C.
- Top rail and anti-climb rails will be 1-5/8" Diameter Sch40
- All posts will be set in 30-36" deep concrete footings. 8" diameter
- 4000 psi concrete for each post base.
- ~72" of 7' tall 9g galvanized 3.5"x5.5" Mesh - Privacy Chain Link walk gate.
- Gate posts will be 2-7/8" Sch40
- Gate frame will be 1-5/8" Diameter Sch40, Bulldog hinges and forklatch

Description	Current PPA Rate	Total PPA Increase	New PPA Rate
Scope Change – ADA Upgrades, Turf Replacement, Security Camera Relocation, and Fence Replacement	$0.1780	$0.0300	$0.2080

ii. Early Termination Fee

The kWh Rate and the Early Termination Values (due to the kWh Rate being updated) set forth in Schedule 2 of the Special Conditions shall be updated per Section 3 below.

3. kWh Rate and Early Termination Fee

PPA Rate Table

Term Year	kWh Rate ($/kWh)	Term Year	kWh Rate ($/kWh)
1	$0.2080	11	$0.2080
2	$0.2080	12	$0.2080
3	$0.2080	13	$0.2080
4	$0.2080	14	$0.2080
5	$0.2080	15	$0.2080
6	$0.2080	16	$0.2080
7	$0.2080	17	$0.2080
8	$0.2080	18	$0.2080
9	$0.2080	19	$0.2080
10	$0.2080	20	$0.2080

Early Termination Fee

Early Termination Occurs in Year:	Column 1 Early Termination Fee where Purchaser does not take Title to the System ($/Wdc including costs of removal)	Purchase Date Occurs on the 91st day following: (Each "Anniversary" below shall refer to the anniversary of the Commercial Operation Date)	Column 2 Early Termination Fee where Purchaser takes Title to the System ($/Wdc, does not include costs of removal)
1*	$7.15		--
2	$6.47		--

3	$5.78		--
4	$5.17		--
5	$4.59		--
6	$4.55	5th Anniversary	$4.05
7	$4.51	6th Anniversary	$4.01
8	$4.47	7th Anniversary	$3.97
9	$4.44	8th Anniversary	$3.94
10	$4.40	9th Anniversary	$3.90
11	$4.36	10th Anniversary	$3.86
12	$4.33	11th Anniversary	$3.83
13	$4.29	12th Anniversary	$3.79
14	$4.25	13th Anniversary	$3.76
15	$4.22	14th Anniversary	$3.72
16	$4.18	15th Anniversary	$3.69
17	$4.15	16th Anniversary	$3.65
18	$4.11	17th Anniversary	$3.62
19	$4.08	18th Anniversary	$3.58
20	$4.04	19th Anniversary	$3.55

4. For the avoidance of doubt, the change in kWh Rate referenced in this Acknowledgement shall not be included in the maximum total increase to the kWh Rate set forth in Schedule 2 of the Special Conditions.

The Parties hereby acknowledge and confirm the terms set forth herein as of the Acknowledgment Effective Date.

County of Fresno, a political subdivision of the State of California

By: _____
Name: Garry Bredefeld
Title: Chairman of the Board of Supervisors of the County of Fresno
Date: _____

FFP BTM Solar, LLC

By: _____
Name: Ruben Fontes
Title: President
Date: 2/27/2026

ATTEST
Bernice E. Seidel
Clerk of the Board of Supervisors
County of Fresno, State of California

By _____
Deputy

For accounting use only:

Org No.: 8935
Account No.: 7431
Fund No.: 1045
Subclass No. 10000